

ADDENDUM ORDER

ORDER NO. 2
DATE: 8/21/26
BID DATE: 8/26/26

NAME OF PROJECT: Desert Road Pump Station

OWNER: Clifton Water District

ENGINEER: SGM

The following changes are hereby made to the CONTRACT DOCUMENTS:

Clarifications

1. The luminaire schedule was inadvertently left off of the drawings. See attached document.

Specifications

1. N/A

Drawings

1. N/A

ADDENDUM #2 ACKNOWLEDGED BY:

Name

Date

PREPARED BY:

Brandyn Bair, P.E.
SGM

List of Attachments:
Luminaire Schedule

LUMINAIRE SCHEDULE

REMARKS:

1. Interior fixtures shall be 3500K, and 80 CRI minimum.
2. Exterior fixtures shall be 3000K, and 70 CRI minimum.

<i>TAG</i>	<i>DESCRIPTION</i>	<i>MOUNTING</i>	<i>MANUFACTURER</i>	<i>MODEL#</i>	<i>VOLTS</i>	<i>WATTS</i>	<i>LAMP</i>	<i>REMARKS</i>
EL	EXIT SIGN WITH INTEGRAL LIGHTS	SURFACE, 8'-0" A.F.F.	COMPASS	CCRG	120	3 VA	LED	
L2	2' HIGH OUTPUT STRIPLIGHT WITH DIFFUSING LENS	SURFACE	TRACE-LITE	VPA-2-30-CP	120	25 VA	LED	1
WP	FULL CUTOFF WALLPACK WITH INTEGRAL PHOTO CELL, BATTERY, & MOTION SENSOR	SURFACE, 9'-0" A.F.G.	COMPASS	CUSO BK	120	10 VA	LED	2